BUCKINGHAM TOWNSHIP

P.O. Box 413, Buckingham, Pennsylvania 18912 Phone (215) 794-8834 • Fax (215) 794-8837 Website - www.buckinghampa.org



Inspections for Swimming Pools, Spas and Hot Tubs

In-Ground Swimming Pool

- Pool Stake Out Zoning Officer will check outline agrees with approved plans
- **Electrical Bonding Inspection** Scheduled with third party electrical inspection agency
- **Steel Framework and Drain Inspection** To be performed after bonding is approved. All steel framework and drains must be in place
- Enclosure Inspection To be performed when fence, gates and door alarms are installed. Pool enclosure must be approved PRIOR to adding water to the pool.
- **Final Electrical Inspection** To be performed when all electrical work is completed.
- **Final Inspection** To be performed when the pool is fully operational and the pool deck is complete

In-Ground / Above Ground Liner Swimming Pool

- Pool Stake Out Zoning Officer will check outline agrees with approved plans
- Wall & Panel Inspection when panels and supports are secured in place and when pool frame has been leveled
- **Electrical Bonding Inspection** Scheduled with third party electrical inspection agency
- **Pool Collar Inspection** To be performed after collar has been placed and before pool is backfilled
- Enclosure Inspection To be performed when fence, gates and door alarms are installed. Pool enclosure must be approved PRIOR to adding water to the pool.
- **Final Electrical Inspection -** To be performed when all electrical work is completed.
- **Final Inspection** To be performed when the pool is fully operational and the pool deck is complete.

Spa / Hot Tub

- **Deck Inspection** If spa / hot tub is on a deck the deck the deck must be designed and inspected by a structural engineer
- Enclosure Inspection To be performed when fence, gates and door alarms are installed. Pool enclosure must be approved PRIOR to adding water to the pool.
- **Final Electrical Inspection** To be performed when all electrical work is completed.
- **Final Inspection** To be performed when the pool is fully operational and the pool deck is complete.